BANGALORE DIVISION.

ADVERTISEMENT.

The 5th December 1889.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 6th January 1890, for constructing a Revenue Survey Office at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1891.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (100) one hundred in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing a Revenue Survey Office at Bangalore"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantity of estimate for constructing a Revenue Survey Office at Bangalore.

Items of Work.	Quantity.	Per.	Rate.	Cost.	Total.
Earthwork excavation forfoundation ..	906	C. Yd.			
Stone in chunam foundaton basement ..	16,290	..			
Brick in chunam superstructure ..	26,608	..			
Do archwork semi-circular ..	2,430	..			
Do segmental	513	..			
Plastering with chunam	469·84	Sqr.			
Pointing with chunam ..	17·10	..			
Whitewashing	196·90	..			
Color washing	272·94	..			
Cornice (1½ feet projection) ..	810	R. Ft			
Do 1 foot do ..	3 20	..			
Do round head of piers ..	208	..			
String course around windows ..	1,044	..			
Flooring with concrete	84·54	Sqr.			
Terrace roofing	217·74	..			
Wood work (teak)	2,062	C. Ft.			
Stone slabs for steps ..	128	S. Ft.			
Doors (excluding frames)	832	..			
Windows do	1,120	..			
Attic windows	336	..			
Glazed semi-circular fan lightso ver doors ..	416	..			
Bamboo matting..	71·13	Sqr.			
Wood oiling	1	Item.			
Zink spouts	1	..			

R. T. SCALDWELL,
Executive Engineer.

CIVIL AND MILITARY STATION, BANGALORE.

IN THE COURT OF THE CIVIL JUDGE.

Mis. Application No. 392 *of* 1889.

Akkaiya .. .. *Applicant.*

In the matter of the property of 1. Ramadu, 2. Muni Lakshmaiya, 3. Munivenkatamma, residents of Old Market, Civil and Military Station, Bangalore, ... *Minors.*

Whereas Akkaiya, resident of Old Market, Civil and Military Station, Bangalore, claiming to be the aunt of 1. Ramadu, 2. Muni Lakshmaiya, 3. Munivenkatamma, the minors above named, has applied for a Certificate of Administration of the property of the said minors Ramadu, Muni Lakshmaiya and Munivenkatamma.

Notice is hereby issued of the said application and Wednesday, the 15th day of January 1890, at 11 A. M., is fixed for hearing the same.

Given under my hand and the seal of this Court this 17th day of December 1889.

W. HILL,